ANGLIA EDGER INSTALLATION INSTRUCTIONS



EXCAVATION DEPTH AND MINIMUM FOUNDATION ⁽³⁾				
NATURE OF PROJECT	GARAGE ENTRANCE		PATIO OR SIDEWALK	
Nature of soil	Clay ⁽²⁾	Sandy	Clay	Sandy
MINIMUM EXCAVATION REQUIRED	16-IN	12-IN	14-IN	10-IN
MINIMUM FOUNDATION THICKNESS 0-3/4" CRUSHED STONE	12-IN	8-IN	10-IN	6-IN
MINIMUM/MAXIMUM UNCOMPACTED INSTALLATION ⁽¹⁾ BED	5/8-IN TO 1-IN	5/8-IN TO 1-IN	5/8-IN TO 1-IN	5/8-IN TO 1-IN
THICKNESS OF THE PAVING STONE	2¾-IN OR 31⁄8-IN	2¾-IN OR 3½-IN	2¾-IN OR 3⅓-IN	2¾-IN OR 3⅓-IN

The information in this table shows the minimum required for a job well done. Anything above this level means improved stability for the whole.

(1) Once compacted, a 1" bed will be reduced down to 5/8".

(2) For certain areas where clay soil is unstable, the minimum excavation required is 24" and the minimum foundation is 525" 21".

(3) Conforms to the recommended ICPI standards (Interlocking Concrete Pavement Institute).