

VGB Series

The AquaStar line of suction outlet covers, compliant with the Virginia Graeme-Baker Pool and Spa Safety Act (ANSI/APSP 16-2011 and NSF/ANSI 50-2009a)

FEATURES

For single or multiple drain use (see installation instructions for plumbing, hydrostatic valve/drain pipe and single or multi-pump connections)

Single

Floor: 268 GPM at 3.1 fps
Wall: 172 GPM at 2.0 fps

Floor/wall: 131 at 1.5 fps
Floor/wall: 87 GPM at 1.0 fps

27.9 square inch opening

#316 stainless steel screws

Manufactured from superior UV-resistant engineered polymers

Three ports: bottom 2½" OD, 2" ID S/S; inside 2" threaded FPT; two 2" threaded plugs included

Permanently attached gasket reduces gasket alignment problems

All components meet or exceed ANSI/APSP 16-2011 and NSF/ANSI 50-2009a national standards and ASTM G154 UV testing exposure

Must use transitional glue when attaching to PVC pipe

Replace every five years from the date of installation

4 per case

Unblockable!



Part # 32CDPHVxxx


Two drains in one!

STANDARD COLORS

- 32CDPHV101 – White
- 32CDPHV102 – Black
- 32CDPHV103 – Light Gray
- 32CDPHV104 – Blue
- 32CDPHV105 – Dark Gray
- 32CDPHV108 – Tan

Also available as sump only
p/n 32CDSBV101
4 per case

VGB 2008 Compliant



1. 32" three-port manufactured vinyl sump bucket
2. 32" channel drain vinyl clamping ring with gasket
3. 32" channel drain vinyl clamping gasket
4. 32" channel drain anti-entrapment suction outlet "pinhole" cover
5. 2" NPT plug, qty 2
6. #10 x 1-1/4" flat head Phillips Type A screw, 316 ss, qty 8
7. #10 x 1" flat head Phillips Type A screw, 316 ss, qty 30